artisan

Sherpa







Doma



Nambu



Temba



Bosti



Kalo



Rigo



Chara



Mera

Pile Fibre **100% NZ Wool** Construction **Chunky Loop Pile**

Machine Gauge 1/8 gauge

Weight $1966 \text{ g/m}^2 - 58 \text{ oz/yd}^2$

Stitch Rate/10cm 24 Density/10cm 768

Pile Height 11mm - plus or minus 5%

Roll Width 3.66m

Primary Backing **Woven Polypropylene**

Secondary Backing **Woven Jute** Insect Resistance **Moth Proofed**

Residential Extra Heavy Duty + Stairs. Contract Heavy Duty + Stairs Grading

Colour variation Colour may vary from batch to batch, and sample to sample - plus or minus 5%

